

TML Testing Report

Author: ADI ChipAgent

Date: April 20, 2026

INTERNAL USE ONLY

Table of Contents

Executive Summary

This report provides an overview of TML (Test Markup Language) testing performed on the V93000 ATE platform for ADI devices.

Test Setup

The following test configuration was used:

Equipment

- Advantest V93000 ATE
- AVI64 instrument cards
- DPVS power supply cards
- HVIN high-voltage cards

Device Under Test

- Device: ADuCM410
- Package: 64-pin LFCSP
- Test board: Rev 2.1

Test Results

Connectivity Tests

All connectivity tests passed successfully:

- Pin continuity: PASS
- Power supply: PASS
- Ground connections: PASS

Functional Tests

1. Digital I/O test: PASS
2. Analog input test: PASS
3. Communication test (SPI): PASS
4. Power consumption test: PASS

TML Code Example

```
testflow connectivity_check {
    setup = {
        Vdd = 3.3V
        Vss = 0V
    }
    execute = {
        run_test("pin_continuity")
        run_test("power_supply_check")
        run_test("ground_check")
    }
    limits = {
        continuity_resistance < 10 ohms
    }
}
```

```
}
```

Issues and Recommendations

WARNING

Warning: Pin 23 showed slightly elevated resistance (8.5 ohms). Monitor this in production testing.

TIP

Tip: Consider adding temperature monitoring for long-duration tests.

Conclusion

All tests completed successfully. Device meets specifications and is ready for production deployment.

Next Steps

5. Validate on 10 additional units
6. Update test limits database
7. Generate characterization report